



COMPLETED PROJECTS

PJ 193 – KCC

Owner	:	Kuwait Port Authority
Construction Managers	:	PROJACS
Piling Contractor	:	Kuwait Bruckner Const Cont Co (KSCC)
Duration of Contract	:	6 Months

Scope of Works

Construction of Bored Piles for the light pole masts having two heights : 38 & 48 meters. The piles are designed with diameter 1500mm. The length for each pile is a soil dependant, but ranges from 6.4 – 10.5 meters.

Total number of Masts = 91