



## CURRENT PROJECTS

**CONSTRUCTION OF PILE FOUNDATIONS ON 400KV OHTL  
STARTING FROM EXISTING LINES NEAR NUWASEEB AND  
CONNECTING TO PROPOSED SUBSTATIONS IN SABAH AL  
AHMED CITY – CONTRACT NO: MEW/C/4291/2011-12**

CLIENT : Ministry of Electricity & Water (MEW)

Main Contractor : KEC International Limited

Sub Contractor : Kuwait Bruckner Construction Cont. Co (KSCC)

Duration of Contract : 6 Months

### **Scope of Works**

Execution of Piling works along with Stub setting relevant to each Four leg Tower. Some special tower consists of four piles per leg having diameter 1000mm

Pile Diameters = 100, 1200 & 1500mm

Total Piles = 560 Nos.

Testing will be performed for each pile diameter consisting of Compression, Tension and Lateral.



