

CURRENT PROJECTS

PJ 212 – FIRST UNITED GENERAL TRADING & CONTRACTING CO.

KUWAIT INVESTMENT AUTHORITY – SHORING, DEWATERING AND PILING WORKS

Owner	:	Kuwait Investment Authority
Contractor	:	First United General Trading & Cont. Co
Piling Contractor	:	Kuwait Bruckner Construction Cont. Co
Duration of Contract	:	1 Year + 1 year maintenance for the Dewatering system

Scope of Works

The following activities will form our scope:-

1. Shoring for an excavation depth of -18.00m with a total exposed shoring area ~ 10,000m² and with multiple anchor layers.
2. Dewatering works for the above pit. Approximate duration – 24 months.
3. Bored piles covering various diameters:-
 - 3.1 Diameter 600mm
 - 3.2 Diameter 800mm
 - 3.3 Diameter 1200mm
 - 3.4 Diameter 1500mm

The depth of the piles ranges from 20m to 40m.

The purpose of the piles to serve as compression for the proposed tower and uplift piles for the multi-level car park.